

Instrukcja użytkowania tunelu ogrodowego

Przed przystąpieniem do pracy należy
zapoznać się z instrukcją !



Zasady bezpieczeństwa

- ✓ Proszę przeczytać wszystkie ostrzeżenia i wskazówki dotyczące bezpieczeństwa i prawidłowego użytkowania produktu. Należy zachować je do wglądu w przyszłości!
- ✓ W czasie montażu proszę zwracać szczególną uwagę na dzieci i inne osoby znajdujące się w pobliżu. Ogranicz dostęp do produktu psom, kotom i innym zwierzętom. Zestaw zawiera małe elementy, które mogą zostać połknięte i ostre krawędzie, które mogą być przyczyną zranienia.

Użytkowanie, przeznaczenie, przechowywanie

1. W okresie zimowym poza sezonami uprawowymi należy zdjąć pokrycie. Przed schowaniem, folie należy dokładnie wyczyścić oraz wysuszyć. Proces składania folii powinien być delikatny, aby nie doprowadzić do przerwania folii w miejscach zagięcia.
2. Podczas prognozy ekstremalnych warunków pogodowych (silny wiatr, śnieg, gradobicie itp.) należy bezzwłocznie zdjąć pokrycie ze stelaża.
3. Producent nie ponosi odpowiedzialności za uszkodzenie tunelu spowodowane trudnymi warunkami pogodowymi.
4. Proszę regularnie sprawdzać stan dokręcenia śrub i innych elementów.
5. Składanie jak i późniejsze użytkowanie produktu ma odbywać się na uporządkowanej, stabilnej oraz równej powierzchni. Producent nie zaleca ustawienia tunelu na powierzchni pochyłej.
6. Nie opieraj żadnych przedmiotów o produkt.
7. Stelaż bez folii należy zakotwiczyć w ziemi, aby uchronić go przed przewróceniem lub ewentualnie rozmontować.
8. Drzwi tunelu muszą być zamknięte na czas intensywnych zjawisk pogodowych (m.in. deszcz, burza, huragan).
9. W wyniku deszczu na górnej części produktu mogą tworzyć się zagłębienia wypełnione wodą. Nadmiar wody należy bezzwłocznie usunąć z zagięć folii.

Zachować szczególną ostrożność !



Montaż

- ✓ Przed rozpoczęciem montażu należy sprawdzić czy zestaw zawiera wszystkie kompletne i sprawne elementy. Nie składać produktu w przypadku stwierdzenia jakichkolwiek uszkodzeń lub braków. Nie ponosimy odpowiedzialności za jakiegokolwiek uszkodzenia zmontowanego produktu.
- ✓ Upewnij się, że produkt jest całkowicie zmontowany jak pokazano na rysunku. Nie ponosimy odpowiedzialności za jakiegokolwiek szkody jeśli uszkodzenie mogło być spowodowane przez nieprawidłowy montaż. Uszkodzenia spowodowane niewłaściwym montażem nie kwalifikują się do uznania gwarancji.
- ✓ Montaż produktu powinien odbywać się w dzień słoneczny oraz bezwietrzny przy temperaturze powyżej 10 stopni Celsjusza. Zjawisko to sprzyja lepszemu ułożeniu folii, gdyż jest ona bardziej elastyczna.
- ✓ Proces naciągnięcia folii powinien odbyć się po około 25 min. od założenia jej. Wtedy pokrycie jest bardziej elastyczne.
- ✓ Nałożone pokrycie ma być napięte. Nie powinno tworzyć luźnych obszarów w tunelu.
- ✓ Tunel musi być odpowiednio zakotwiczony w ziemi. Należy wkopać nadmiar folii (tzw. fartuch ziemny) w ziemię. Proszę nie obsypywać oraz nie obkładać pokrycia ciężkimi przedmiotami.
- ✓ Podczas montażu użyj rękawic ochronnych.
- ✓ Zaleca się montaż w minimum 2 osoby.
- ✓ Przygotuj narzędzia, które mogą się przydać m.in. zestaw kluczy i śrubokrętów (zestaw nie zawiera).
- ✓ Dodatkowe wzmocnienie tunelu (dodatkowe kotwy do przytwierdzenia do ziemi, podpory łuków od wewnątrz), które ma za zadanie ochronić tunel przed trudnymi warunkami atmosferycznymi powinno odbywać się we własnym zakresie.
- ✓ Produkt powinien być montowany w miejscach osłoniętych (nie na wolnej przestrzeni).
- ✓ Producent zastrzega sobie prawo do zmian i modyfikacji w instrukcji.
- ✓ Podczas użycia opakowania pomyśl o środowisku.

Importer:

CHOMIK S.J.

ul. Cegielniana 875

32-420 Gdów

Tel: +48 122514027

www.chomik.pl



Instruction for use of garden tunnel

Before starting work, you should familiarize yourself with the instruction! Exercise particular caution!



Safety rules

- ✓ Please read all warnings and safety instructions regarding the safe and proper use of the product. Keep them for future reference!
- ✓ During assembly, please pay special attention to children and other people nearby. Limit access to the product for dogs, cats, and other animals. The set contains small parts that can be swallowed and sharp edges that can cause injury.

Use, purpose, storage

1. During the winter and off-seasons, it is necessary to remove the cover. Before storing, the film should be thoroughly cleaned and dried. The process of folding the film should be gentle to avoid tearing it at the crease points.
2. During extreme weather conditions (such as strong winds, snow, hail, etc.), it is essential to immediately remove the cover from the frame.
3. The manufacturer is not responsible for damage to the tunnel caused by adverse weather conditions.
4. Please regularly check the tightness of screws and other components.
5. Folding and subsequent use of the product should take place on an organized, stable, and level surface. The manufacturer does not recommend placing the tunnel on an inclined surface.
6. Do not lean any objects against the product.
7. The frame without the film should be anchored in the ground to protect it from tipping over or, if necessary, disassembled.
8. The tunnel doors must be closed during intense weather conditions, including rain, storms, and hurricanes. Due to rain, depressions filled with water may form on the upper part of the product. Excess water should be promptly removed from the folds of the film.



Assembly

- ✓ Before starting assembly, please check if the kit contains all complete and functional components. Do not assemble the product if any damage or missing parts are found. We are not responsible for any damage to the assembled product.
- ✓ Ensure that the product is fully assembled as shown in the diagram. We are not responsible for any damages if the damage could have been caused by incorrect assembly. Damages resulting from improper assembly do not qualify for warranty coverage.
- ✓ The product assembly should take place on a sunny and windless day with a temperature above 10 degrees Celsius. This condition promotes better film placement, as it is more flexible.
- ✓ The process of stretching the film should occur approximately 25 minutes after its placement. At that time, the cover is more flexible.
The applied cover should be tight and should not create loose areas in the tunnel.
- ✓ The tunnel must be securely anchored in the ground. Excess film (the so-called ground apron) should be buried in the soil. Please do not mound or surround the cover with heavy objects.
- ✓ During assembly, use protective gloves.
- ✓ It is recommended to assemble with a minimum of 2 people.
- ✓ Prepare tools that may come in handy, including a set of wrenches and screwdrivers (not included in the kit).
Additional reinforcement for the tunnel (extra anchors for securing to the ground, support for arches from the inside), which is intended to protect the tunnel from adverse weather conditions, should be carried out at your own discretion.
- ✓ The product should be assembled in sheltered locations (not in open spaces).
- ✓ The manufacturer reserves the right to make changes and modifications to the instructions.
- ✓ Consider the environment when disposing of the packaging.

ENG